PERMIT

CITY OF NAPOLEON 255 W. RIVERVIEW AVE NAPOLEON, OHIO 43545

DIVISION OF BUILDING & ZONING PH (419) 592-4010 FAX (419) 599-8393

PERMIT NO: 1703 DATE ISSUED: 06-26-03 ISSUED BY: TJK

JOB LOCATION: 435 FILLMORE ST

EST. COST: 23065.00

LOT #:

SUBDIVISION NAME:

OWNER: DRUMMOND, COLLEEN ADDRESS: 435 FILLMORE ST CS2: NAPOLEON, OH 43545

AGENT: TRI-COUNTY ROOFING I ADDRESS: 13771 CO RD 162 CSZ: PAULDING, OH 45879

PHONE: 419-592-4432

PHONE: 419-399-3964

USE TYPE - RESIDENTIAL:

OTHER:

ZONING INFORMATION

DIST: LOT DIM: AREA: FYRD: SYRD: RYRD: MAX HT: # PKG SPACES: # LOADING SP: MAX LOT COV:

BOARD OF ZONING APPEALS:

WORK TYPE - NEW: REPLMNT: ADD'N: ALTER: REMODEL:

WORK INFORMATION

SIZE - LGTH: WIDTH: STORIES: LIVING AREA SF: GARAGE AREA SF: HEIGHT: BLDG VOL DEMO PERMIT:

WORK DESCRIPTION REMOLDELING

FEE DESCRIPTION PAID DATE

FEE AMOUNT DUE

BUILDING PERMIT PLUMBING PERMIT ELECTRICAL PERMIT MECHANICAL PERMIT

59.00 9.00 9.00 5.00

TOTAL FEES DUE 82.00

DATE

APPLICANT SIGNATURE



ş an 2

TRI-COUNTY ROOFING INC

13771 CR 162 Paulding OH 45879 419/399-3964 419/399-9662

Arrention: Brent / Perm Office location:	
Fax number:	Phone number: 419/399-3964

Total pages, including cover:

Comments:

. 12 v
435 EIIIMORE
455

			āl	

Colleen Drummond 435 Fillmore St. Napoleon, Ohio

Unit#11

City of Napoleon Rehab Specifications

No Windows

phone (419) 592 - 4432

JAN

1. Sidewalk: Remove all of the front sidewalk (approximately 50' linear feet). Remove the steps to the front entry door. Construct forms for sidewalk and steps to the front entry. Approach dimensions... 4"thickness X 5'wide X 9' length. Sidewalk 4" thickness X 4' wide X approximately 50' length.

Lay 2" of river sand and properly tamp and prepare bed to pour approaches and sidewalk. Lay and tie together ½" rebar (on 2' spacing) in constructed approach and sidewalk forms. Pour sidewalk and steps with 2,500 pound concrete mix. To the sidewalk, trowel in expansion joints every 3' and properly trowel edges. Broom finish the surface of the pad and sidewalk. Apply concrete sealer to surface of sidewalk and pad.

Contractor must contact housing inspector for pre-pour inspection of pad and sidewalk preparation.

5+1

1,625

600

10 16-62. Roofing: Remove all of the existing roof covering, down to the sheathing. Mechanically 1016-62 Grasten 7/16 roof sheathing to roof deck. Secure 15# felt to roof sheathing and secure aluminum 1913 Grasten 7/16 roof perimeter. Install, per manufacturer's instruction, minimum 240# test weight, Grass A fire rated, 30 year warranty fiberglass dimensional roof shingles and cap shingles.

Properly flash all roof outlets. Homeowner to select shingle color.

19x 33(.27

6/12

Insulation: Install blocking to the top and bottom of knee wall. Install blown cellulose to the floor area of open knee wall and the ceiling of the upper floor. All electrical junction boxes must be properly flagged and heat producing devices blocked.

Remove existing siding and fan-fold insulation board as needed. Install blown cellulose insulation, minimum of 3.25 lbs / cu. ft., in the sidewalls of the entire structure. All holes bored 30x/6-40 through the walls must be properly plugged and secured. Re-secure the removed fan-fold and

3127/6 41 diding.

Install R-19 batt insulation to the perimeter joists (rim and sill).

12×10:120

7 × 10 - 10 4. Exterior doors: Replace the front and rear entry doors with Stanley, Therma-Tru, or equal quality pre-hung insulated steel doors with light. Doors must be factory painted or contractor applied (TWO coats). Homeowner to select door style and color from contractor options.

Install Kwikset-Belaire Series or equal quality lockset with dead-bolt lock. Locks must be

77 keyed alike.

Re-install the existing storm doors to the front and rear entry doors.

BU



Eny NoTrim

5. Replacement windows: Install white vinyl, double-hung replacement windows (Certainteed, Seaway, Great Lakes, or equal quality) to all of the windows throughout the structure.

NOTE: All window weight ropes/cables, pulleys and weights must be removed and weight pockets must be insulated. The interior and exterior perimeters must be properly caulked with window/door caulk.

2 hupper

Replace all of the basement windows with white vinyl "hopper" windows.

6. Plumbing: 2 Story Basement / Craw!

DWV - Replace all of the ABS drain lines with PVC drain/waste/vent pipe.

Water supply lines – Replace all water supply lines, from the main to all fixtures, with 3/4" supply lines, reduced to ½" at each fixture. Install shut off valves to all fixture supply lines. Install a Watts 007 (or equal) double check valve back flow prevention assembly complete with test ports to the main water line.

Water heater - Install a 3/4" copper extension from the temperature relief valve to within 3" of floor.

Kitchen – Install shut-offs to the water supply lines of the sink faucet. Replace the sink drain trap with a "p" trap.

Bathroom - Install shut-offs to the water supply lines of the sink faucet. Replace the sink drain trap with a "p" trap.

NOTE: All plumbing to conform to The Ohio Plumbing Code. Plumbing contractor is responsible for repairing all areas damaged by plumbing work. All repairs to match existing surfaces.

7. Electrical: Replace and remove all non-grounded electrical wire with "romex"-type electrical wire with ground.

Basement – Install junction box cover to open junction boxes. GFCI protect the non-appliance receptacles.

Install a single recep, at the clothes washer.

Kitchen – Install the open junction, located under the sink, in a junction box with cover. GFCI protect the receptacle south of the sink and install ONE (1) additional gfci receptacle north of sink.

Livingroom – Install TWO (2) additional wall receptacles. Locate one on the north wall, east of the entry door and one on the west wall.

Bathroom - GFCI protect the receptacle near the vanity.

Connect exhaust vent duct to the exhaust fan and properly direct to the homes exterior and terminate with a louvered cover.

Computer room - Install ONE (1) additional wall receptacle. Locate on the east wall.

Bed #1 (1st floor) - Install TWO (2) additional wall receptacles. Locate at each the south and west walls

Replace the closet light with a wall switched enclosed flourescent fixture.

Closet - Replace the closet light with a wall switched enclosed flourescent fixture.

PL-9.00

043

Stairway – Install TWO (2) three-way wall switches located at each the top and bottom landing to control the light at the top landing.

Upper bed -east - Install TWO (2) additional wall receptacles. Locate on each the north and east walls.

Install electrical wire feed and TWO (a) 8' length electric baseboard heaters with individual thermostat controls to heat the area.

Upper bed - west - Install THREE (3) additional wall receptacles. Locate on each the north, south, and west walls.

Install electrical wire feed and TWO (*) 8' length electric baseboard heaters with individual thermostat controls to heat the area.

Replace the closet light with a wall switched enclosed flourescent fixture.

Smoke detectors – Install FIVE (5) U.L approved, hardwired smoke detectors with battery back-up. Wire detectors in series. Locate at each of the following locations.. basement, bedroom #1, livingroom, stair landing (bottom), stair landing (top).

CO detector – Install TWO (2) U.L approved hardwired, with battery back-up CO detectors. Locate in each the basement and outside the 1st floor bedroom.

Exterior – Install TWO (2) exterior gfci receptacles, complete with weather resistant cover. Locate ONE (1) at each the front and rear entry.

GFCI protect the garage wall receptacles.

NOTE: All electrical work must conform to NEC and be performed by qualified technician(s).

8. Furnace: Replace the furnace with a 80%+ efficient natural gas forced air furnace. Furnace must be properly sized (supply sizing chart to housing specialist). Connect the furnace to the existing supply/return ducts. Install a liner kit, complete with cap, in the chimney "chase" to properly direct water heater and furnace flue gases outside the home. Furnace wire must be installed in conduit. New furnace system must have new pre-manufactured filter assembly, filter, and thermostat. Upon completion of system installation, fire furnace and perform diagnostic testing to assure proper system function.

Replace all non-black iron gas supply line, from the main to all gas appliances. Install drip leg and shut-off valve at each appliance.

Furnace installation to conform to NFPA-54 and be performed by qualified HVAC technician(s).

9. Interior carpentry: Secure hand railing with spindles along both side of stairs.

450

EL-9.00

TOTAL PROJECT BID

23.065

		•	
			•

CITY	OF NAPOLEON	OHIO	PERMIT	APPLICA	TION
7 Hds /	UPLICATION IS FOR EXIMENTIAL CONSTRUCTOR	ON THICK LEDGED BY M.	The second second		77011
F 35	DPLICATION IS FOR RESIDENTIAL CONSTRUCTS	NA DICERDING ROTT	DRING' REPORTERENT" MCC/MO	ng, mechanical demolitio	n, remodeling

DATE 10-210-03	JOB LOCATION	
LOT#	SUBDIVISION NAME	_
OWNER COLLOOD Dru	mmond PHONE 592-4432	
OWNER ADDRESS 435	Fillmore St CITY Napoleon 2119 43545	<u>_</u>
CONTRACTOR Tri-Coun	ty Kooting, Inc. PHONE 419-399-39104	
CONTRACTOR ADDRESS 137	TI C.R. 162 corr Pacifing 20 458	79
CONTRACTOR FAX # 419-3	9-9662 CELL PHONE (Opt.)	2000
DESCRIPTION OF WORK TO BE	ERFORMED: Total Rehab	-
	BE PERFORMED: 23,0105	
WORK INFORMATION		-
BUILDING: Basement Floor Area	Sq. Ft. 1st Story Living Area Sq.	Ft
	Sq. Ft. Garage Floor AreaSq.	
BUILDING SIZE: Length	Width Stories Height DEMO VOL	
Masonry Contractor 141 Bu Address	City St Zip	-
	Phone Fax City St Zip	
Plumbing Contractor	Phone Fax	from s
Heating Contractor <u>Eardre</u> Address	O HVAC Phone 542-9013 Fax 542-0111 City St Zip	
	Phone Fax City St Zio	-
Other Contractor attach information.	ver s g ,es	==>
ZONING INFORMATION (to be co	SYSB RYSB Max Ht ft Max Cov %	
ity dente the belief agree to comply with all explicable tily of a server by the belief assesses of the tity of Magazana.	apoleon Codes de Ordinances while performing the work havin described. Lundewated that all work for which a permit is strainly required to be	
pplicant Signature	Date	

CITY OF NAPOLEON INSPECTION FORM

PERMIT #: 170	3
DATE ISSUED: 0	06-26-2003
JOB LOCATION:	435 FILLMORE ST
OWNER: DRUMMO	ND, COLLEEN
OWNER PHONE: 4:	19-592-4432
CONTRACTOR: TH	RI-COUNTY ROOFING INC
CONTRACTOR PHO	ONE:419-399-3964
WORK DESCRIPT	ION: REMOLDELING
PLUMBING: U	JNDGR RGHIN FINAL 8-28
\$	SEWER INSP
MECHANICAL: (JNDGR RGHIN FINAL
I	FURNACE REPLC AIR COND
ELECTRICAL: U	JNDGR RGHIN FINAL \$\&\mathcal{2}-2\&\eta\$
\$	SERV UPGR
BUILDING: S	SITE FTG FNDT
2	STRUC ROOF EXT
7	/ENT ACCES EGRS
S	SMKDT FINAL <u>8-28</u>
3	ISSUE TEMP OCCUP ISSUE OCCUP
STRG SHED: SIT	TE FINAL
SIGN: FTO	FINAL
FENCE: SIT	TE FINAL
MISC INSP:	
NOTES:	
	CIALS: AM
INSPECTOR THIT	TALS: UDIII

				T Z FILL
				usel MT4u
		J P. 20-41	RESTAURS NO	
			HAROLE CLUE	BO PLENO
			gage gest to by	349
		w rōe	Augustinus - mi	Table
			e of the so	The Thirty
			N DE VENERALS	ERAN UNTE
S. S. A. S.			4.F8 (1/4)	- 1. 5° vo
	ANT I		9,500	ها جهادور دی
	Xc A			
46.0	Javit		1)2/27[5]	
	deces.			
	MASS AND THE RESERVE TO THE RESERVE	3		
				No.
		LABLY		H- 1386
			119	. 92
		Tollier =	79.71	4.4.1.
				Tell the fo
		V 8		
		A STATE OF THE STA		#. 1° 8°
		*		