

City of NAPOLEON, OHIO

255 WEST RIVERVIEW AVENUE, P.O. BOX 151 NAPOLEON, OHIO 43545-0151 (419) 592-4010 FAX (419) 599-8393

November 4, 1997

Mayor Donald M. Stange

Members of Council
Michael J. DeWit, President
Dennis Filgor
James Hershberger
Glenn A. Miller
Travis B. Sheaffer
Char Weber
Terri A. Williams

City Manager Marc S. Gerken, P.E.

Finance Director Gregory J. Heath

Law Director David M. Grahn

City Engineer Adam C. Hoff, P.E. Mr. Rex Walker Walker Mortuary, Inc. 333 West Main Street Napoleon, Ohio 43545

Re: City of Napoleon

Walker Mortuary Site Improvements

Dear Mr. Walker:

Per my correspondence of October 14, 1997, we have reviewed the site and developed a proposed location for a 2x2 catch basin in the alley to the east of your facility. The top of the casting will be set at elevation 681.75 and the invert of the new six (6) inch tile to the north will be elevation 677.30. Enclosed is a sketch showing this proposal. Please have your consultant revise the proposed site plan for your facility to reflect the above noted changes and those stated in my October 14th correspondence and resubmit the plan for final review and approval.

If you have any questions, please call me.

Yours truly,

Adam C. Hoff, P.E. City Engineer

ACH:rd Enclosure

cc: Mr. Marc S. Gerken, P.E.; City Manager

Mr. Brent Damman, Bldg./Zoning Administrator

Mr. Rex Moll, Construction Inspector


Mr. Fred Arn, Poggemeyer Design Group

Mr. Vern Masters, Vernon Nagel, Inc.

c: lotsuite wordpro docs cityengr walkersiterev lwp11,4/97, 10:06AM

ENG-018 Permanent Record Retention

MAIN STREET 131.93 N 62'30'16" E 1531.F. @ 0.50% LOT #1 LOT #2 EX BLD 96.33 / / / / / 2x 2 C. B. TOP=681.75 — INV. 6"N=677.30 - CONCRETE WALK 16.5' ALLEY CUT EXIST. PVMT. NEW ADDITION MATCH EXIST H EXIST



Be Removed



City of NAPOLEON, OHIO

255 WEST RIVERVIEW AVENUE, P.O. BOX 151 NAPOLEON, OHIO 43545-0151 (419) 592-4010 FAX (419) 599-8393

October 14, 1997

City of Napoleon

Walker Mortuary Site Improvements

Mr. Rex Walker Walker Mortuary, Inc. 333 West Main Napoleon, Ohio 43545

Mayor Donald M. Stange

Dear Mr. Walker:

Members of Council
Michael J. DeWit, President
Dennis Fligor
James Hershberger
Glenn A. Miller

Travis B. Sheaffer Char Weber Terri A. Williams

City Manager Marc S. Gerken, P.E.

Finance Director Gregory J. Heath

Law Director David M. Grahn

City Engineer Adam C. Hoff, P.E. Per our recent meeting with City Manager, Marc Gerken, the City will have our contractor, Vernon Nagel, Inc., install a new six (6) inch tile in the alley to the east of your facility to a point even with the northerly line of the vacated alley, as shown on the attached sketch. A new 2x2 catch basin will be provided at that point and the alley will be regraded to prevent surface water from discharging to the south. The final location and elevation of the outlet will be determined as soon as possible. In the meantime, please have the site plan revised to reflect the modifications noted in my correspondence of October 10, 1997 as well as the changes noted herein.

As we discussed, it will be your responsibility to extend a new six (6) inch drain to the proposed alley location. This drain will be connected in the spring when the West Main Street storm sewer is constructed. In the interim, as stated in my prior correspondence, the storm water may discharge as originally designed. When the sewer is constructed within the alley by the City, plugs will have to be placed by your contractor in the six (6) inch drain at the south edge of your property.

If you have any questions or require further information, please call me.

Yours truly,

Adam C. Hoff, P.E. City Engineer

ACH:rd

Attachment cc: Mr. Marc S. Ge

cc: Mr. Marc S. Gerken, P.E.; City Manager

Mr. Brent Damman, Bldg/Zoning Inspector

Mr. Rex Moll, Construction Inspector

Mr. Fred Arn, Poggemeyer Design Group

Mr. Vern Masters, Vernon Nagel, Inc. c: lotsuite wordpro docs cityengr walkerwalker.lwp10/14/97, 10:14AM

ENG-018 Permanent Record Retention



City of NAPOLEON, OHIO

255 WEST RIVERVIEW AVENUE, P.O. BOX 151 NAPOLEON, OHIO 43545-0151 (419) 592-4010 FAX (419) 599-8393

October 10, 1997

Mayor Donald M. Stange

Members of Council Michael J. DeWit, President Dennis Fligor James Hershberger Glenn A. Miller Travis B. Sheaffer Char Weber

City Manager Marc S. Gerken, P.E.

Terri A. Williams

Finance Director Gregory J. Heath

Law Director David M. Grahn

City Engineer Adam C. Hoff, P.E. Mr. Fred Arn Poggemeyer Design Group 1168 North Main Bowling Green, Ohio 43402

Re:

City of Napoleon

Walker Mortuary Site Improvements

Dear Mr. Arn:

Based upon my review of the site plan submitted for the referenced project, I have developed the following comments:

1.) The site plan indicates two (2) proposed catch basins connecting into the existing six (6) inch tile going south off of the Walker Mortuary property. This existing six (6) inch connects to the City's sanitary sewer system. Therefore, the catch basins cannot ultimately be connected to it. A new storm sewer will be extended along the south side of West Main Street in June of next year.

Please revise the plans to provide for a connection extended to the south right-of-way line to meet the proposed storm sewer along West Main Street. When the proposed storm sewer on West Main is constructed, this connection will be made. In the interim, the new catch basins may be connected to the existing sewers. However, once the new storm sewer is constructed and in operation, the connection to the existing six (6) inch tile must be plugged.

2.) The proposed storm sewer on West Main Street and Scott Street was not sized to carry flows produced from a totally impervious area such as a parking lot. The sewer was sized based upon a typical residential area. Therefore, the flow from the proposed parking lot at Walker's will need to be metered with on-site detention provided. This may be accomplished by constructing a

Mr. Fred Arn Page Two October 10, 1997

ことの場合で

twelve (12) inch outlet out toward Main Street and providing a reducer and a six (6) inch connection to the storm sewer.

3.) The current parking plan and traffic islands, as proposed, are not acceptable. The minimum aisle width permitted behind 90° parking spaces is twenty-four (24) feet. The five (5) spaces along the west property line show only a twenty-three (23) foot aisle. The "L-shaped" island near the northwest corner of the proposed garage should be deleted. This will eliminate the aisle width concern.

The proposed island located just to the south of the vacated alley and around the existing large silver maple will most likely kill this tree. It is our recommendation that this island and tree be removed.

4.) Due to the existing angle parking along the west property line, we will require that directional arrows be placed on the pavement and signage be provided to clearly define the entrance and exit at the site and the flow of traffic through the site.

If you have any questions or require further information, please call me.

Yours truly,

Adam C. Hoff, P.E.

City Engineer

ACH:rd

cc: Mr. Marc S. Gerken, P.E.; City Manager

Mr. Brent Damman, Bldg/Zoning Administrator

Mr. Rex Walker

c:\lotsuite\wordpro\docs\cityengr\walkerernfred.lwp10/10/97, 8:35AM

ENG-018 Permanent Record Retention



ARCHITECTS-ENGINEERS-PLANNERS

1168 North Main Street Bowling Green, Ohio 43402 (419) 352-7537 Fax (419) 353-0187

☐ 602 Chillicothe Street Suite 117 Portsmouth, Ohio 45662 (614) 354-1909 Fax (614) 354-2880 417 Wayne Avenue P.O. Box 7040 Defiance, Ohio 43512 (419) 782-3067 Fax (419) 784-5293

425 Metro Place North Suite 600 Dublin, Ohio 43017 (614) 889-7747 Fax (614) 889-8217

25 Walnut Street Lexington, Ohio 44904 (419) 884-2001 Fax (419) 884-0471

☐ 5440 Fulton Drive, N.W. Suite 211 Canton, Ohio 44718 (330) 966-8808 Fax (330) 966-8809

LETTER	OF '	TRANSMI	TTAL
--------	------	---------	------

Terrary.			LETTER OF II	RANSIVII	ITAL	
то: Вед	T DA YOF P WI.R APOLE	MMAN JAPOLE WERVIE N, OH	ON AUE 43545	ATTENTION		JOBNO7393.002 FUNERAL HORAE
WE ARE S	ENDING YOU	Attached	☐ Under separate co	ver via (MA	the follow	ing itoms:
Shop di		Prints Change o	Plans		☐ Samples	
COPIES	DATE	NO.			DESCRIPTION	
(SITE PLA	N-RE	ursen	
			COTORM V	MATER	CACCS	
THESE ARE TR						
For approval For your use			No exceptions noted Exceptions noted			copies for approval
As requested			Revise and resubmit			copies for distribution corrected prints
For review ar]			oonooted prints
REMARKS						
COPY TO						
			•	PO	GGEMEYER I	DESIGN GROUP, INC.
					mat	2,000
•				SIGNED:	PLE	417

)						2		LOCATION		CA	ד (- ג	<u> </u>		UISK I UKM U
								Ŀ									TON -	-	בכטב	טקבר) 	ATI	CIVIAI
												,			7	26	Δ A.	ESIG	CALCULATED BY	NA	-	9 8	
			8														M >	DESIGN FREQUENCY	Ц Т	PROJECT NAME HANDING TOWNS IN INC. LOCATION NAME TO THE COLOR OF THE C		RATIONAL	
															۵	0	C	100		A LANGE		F	
		-													8	8	Δ Τ	NCY.	. UAIE	, ,	¥_)R	
-	T	1														14	M F		- 1			FORMULA COMPUTATION	
-	+	+													W.		110	344		STATE OF	Š		
_	1														D D	E -	NIENSIY	^	3	N. S. N	<u> </u>	00	
					٠.,												XIIY		단		7	MF	
							·								=	N.	ΔCA		CHECKED BY		2		
															124	Ü	MCA.]	Ú H		4	A	4 3
			8											•	10.	こし	S YR			N		j.	
	Ī																∏ <u>ફ</u>	7 2	֡֝֞֝֝֡֜֝֞֜֝֞֜֝֞֜֜֝֟֝֟֝֓֓֓֟֜֜֝֟֜֟֜֟֝֟֜֟֝֓֓֓֓֟֜֜֜֟֜֟֜֝֟֜֝֓֡֡֡֡֡֡֝֡֡֡֜֝֡֡֡֡֝֡֡֡֡		g P		
+		+															-YR LGTH	그 92	DAIE -	1		ORM	
+	1	+													6 -	0	H SIZE	1	- 1	1	2	Z	
	t	+		7							*				2,0	162	E SLOPE				۲		
+	+	+	9													-	¥ %				Ĉ		
															5.0	W. W	VELOC	- 1	JOB NO.	5 '	3	PO	
							ਜ਼										FRICTION SLOPE		1	SHEET NO.		POCCEMEYER DESIGN GROUP, ARCHITECTS + ENGINEERS + PLANNERS ROWLING CREEN OFFI	
	d																E S	0.00		¥0.	5	R DES	
			-														XADE I	U	V		2	IGN G	
			o			a)											SLOPE EL YR PIPE EL		_ PHASE	2		ROUP, INC.	
										-							ELEV		ř	í		ýĊ.	

