

THE CITY OF NAPOLEON
BUILDING & ZONING DEPARTMENT

255 W. RIVERVIEW

(419)592-4010

Sidewalk/Curb Replacement Permit

Page 1 of 1

Permit Number: SW2005-26

Printed: 8/30/2005

Property Address: 225 Northcrest Dr

Applicant B & B Concrete
Address: 613 Arden Ct

Approval Date: 8/30/2005

Napoleon, OH 43545

Phone: 419-344-2929

Owners

Name: Mr. Daniel Badenhop
Address: 225 Northcrest Dr

Contractors B & B Concrete
Address: 613 Arden Ct
Napoleon, OH 43545


Phone 419-344-2929

Fees and Receipts:

Number	Description	Amount
FEE2005-666	Sidewalk/Curb	\$25.00

Total Fees: \$25.00

Description of work to be done: Sidewalk replacement



Applicant signature: _____ **Date:** _____

CITY OF NAPOLEON GENERAL PERMIT APPLICATION
THIS APPLICATION IS FOR RESIDENTIAL CONSTRUCTION INCLUDING BUILDING, ELECTRICAL, PLUMBING, MECHANICAL, DEMOLITIONS, REMODELING.

DATE: _____ **JOB LOCATION:** _____

OWNER: Badenhop **PHONE:** _____

OWNER ADDRESS: 225 Northcrest **CITY:** Napoleon **ZIP:** 43345

CONTRACTOR: B+B Concrete **PHONE:** 419-344-2929

CONTRACTOR LICENSED WITH THE CITY OF NAPOLEON?: YES: NO: _____

Is any of this job going to be subcontracted out? Yes: No: _____

If yes to whom: Nagel

DESCRIPTION OF WORK TO BE PERFORMED: _____

PLEASE MARK THE TYPE OF WORK YOU WILL BE PERFORMING

- | | |
|---|--|
| <input type="checkbox"/> A/C ADD ON | <input type="checkbox"/> REMODELING |
| <input type="checkbox"/> BOILER REPLACEMENT | <input type="checkbox"/> ROOFING |
| <input type="checkbox"/> CURBING | <input type="checkbox"/> SEWER REPAIRS** |
| <input type="checkbox"/> DECKS * | <input checked="" type="checkbox"/> SIDEWALK* |
| <input type="checkbox"/> DRIVEWAY* | <input type="checkbox"/> SIDING |
| <input type="checkbox"/> ELECTRICAL SERVICE UPGRADE | <input type="checkbox"/> STORAGE SHED* |
| <input type="checkbox"/> ELECTRICAL SERVICE NEW | <input type="checkbox"/> SWIMMING POOL* |
| <input type="checkbox"/> FENCE* | <input type="checkbox"/> FURNACE REPLACEMENT |
| <input type="checkbox"/> ADDITIONS* | <input type="checkbox"/> TEMP ELECTRIC |
| <input type="checkbox"/> FURNACE NEW | <input type="checkbox"/> WATER TAP (size _____") |
| <input type="checkbox"/> LAWN METER | <input type="checkbox"/> WINDOWS |
| <input type="checkbox"/> PLUMBING | <input type="checkbox"/> ZONING |

***PLEASE INCLUDE A PICTURE SHOWING MEASUREMENTS FROM EXISTING STRUCTURES AND PROPERTY LINES. INDICATING THE TYPE OF WORK YOU WISH TO PERFORM.**

**** IF WORK REQUIRES GOING INTO THE STREET A STREET BOND IS REQUIRED!**

FOR PERMIT COSTS PLEASE FILL OUT REVERSE SIDE.



CITY OF NAPOLEON
ENGINEERING DEPARTMENT

255 W. Riverview Avenue, PO Box 151, Napoleon, OH 43545
Phone: 419-592-4010 - Fax: 419-599-8393

FORMAL NOTICE

RESOLUTION OF NECESSITY
(RC 729.03)

Mayor
J. Andrew Small

Members of Council
Glenn A. Miller, President
Terri A. Williams
James Hershberger
Travis B. Sheaffer
John A. Helberg
Steven C. Small
Michael J. DeWit

August 15, 2005

Daniel Beckenhop
255 Northcrest Dr
NapoleonOH43545

City Manager
Dr. Jon A. Bisher

This is FORMAL NOTICE that on July 18, 2005, the Council of the City of Napoleon, Ohio passed Resolution No. 069-05, declaring the necessity of constructing certain sidewalks.

Finance Director
Gregory J. Heath

Under the Resolution you are required to construct the sidewalks abutting your property, 225 Northcrest Dr. in accordance with the plans and specifications filed in the office of the Clerk of Council of the City of Napoleon, Ohio.

Law Director
David M. Grahn

In the event construction is not completed within 30 days from the date of service of this notice, the Council of Napoleon, Ohio will cause it to be done and the entire cost assessed against your property as provided by law.

City Engineer
Joseph R. Kleiner, P.E.

If you are intending to complete the project yourself or by an independent contractor, a permit is required from the Engineering Department pursuant to Sec. 913.04 of the Codified Ordinances of the City of Napoleon, Ohio. Specifications and minimum building requirements may be obtained from the Office of the City Engineer. The City Engineer can be contacted at (419)592-4010, or in person at City Hall located at 255 West Riverview, Napoleon, Ohio.

Issued by order of the Council of the City of Napoleon, Ohio.



Gregory J. Heath, Finance Director

Attachments
Cc: Mr. Joe Kleiner, City Engineer

CITY OF NAPOLEON

RESIDENTIAL SIDEWALK SPECIFICATION

I. WORK INCLUDED:

- A. Under this item the Contractor shall improve by construction, reconstruction or repairing as is necessary public sidewalks between limits established by the Engineer.
- B. Sidewalks shall be at least four (4") inches in thickness and in driveway crossings six (6") inches in thickness. When sidewalks abutt with the curb, the width shall be five (5') feet or as wide as the existing sidewalks; in either case, a minimum width of four (4') feet shall be adhered to. Edge of walks adjacent to the property line of the street shall be placed at least one (1') foot from the property line or meet existing sidewalks. The Engineering Department will give line and grade.
- C. Old concrete sidewalk material shall be removed and granular material used for fill if necessary to meet grade.
- D. All work shall conform to the standard specifications published by the Ohio Department of Transportation (O.D.O.T.) and the City, in effect at the date of contract and the requirements under these specifications.
 1. Referenced O.D.O.T. specifications as follows:
 - 608. concrete walks
 - 499. concrete
 - 511.12 depositing and curing concrete in cold weather

II. MATERIALS AND FINISH:

- A. A minimum 4" thick of crushed limestone base shall be provided and compacted in place. #57, #411, or #304 limestone to be used.
- B. The concrete mix shall be a minimum of a 6' bag mix with 5 to 6% air entrainment. All surface area shall be broom finished and sealed with an Engineer approved concrete sealer. All joints shall be trowel-cut with a maximum joint spacing of 5 feet. The depth of cut shall be a minimum $\frac{1}{2}$ of the thickness of the slab. The final trowel-cut and edging shall be done after the final brooming. Expansion joints shall be placed at a maximum of 40 feet and at all intersecting walks.