EAST WASHINGTON ST.

PERRY ST.

MONROE ST.

PROVIDE NEW DAMPROOFING-FND'TION 4" PERFORATED PVC TILE NORTH HALF OF BUILDING, HATCHED AREA

NEW WATER MAIN TO TIE INTO EXIST. WATER MAIN IN ROAD

EXIST. SANITARY / STORM M.H.

EXIST. ELECT. TO REMAIN

BRICK PAVER SEE DET. 2/SP-1

RECONSTRUCTION OF FOUNTAIN ALTERNATE C-4 SEE SHT. A-1

EXISTING CONC. WALK TO REMAIN

2 SIGNS

NEW BENCH & CONC. PAD

WASTE BIN

TEL. ON PAD ON CONC. PAD

LAWN

MAIL BOX

NEW M.H.

RELOCATE TELE

NEW LANDING, STEPS AND SIDEWALK SEE DET. A/A-2

NEW FW DOWN-SPOUT LINES

REMOVE TOPSOIL & GRADE. REPLACE W/ NEW ASPHALT PAVING FLUSH W/ EXISTING DR. AT CONTRACT LIMIT LINE SEE DET. 5/SP-1

FLAT ROOF

EXIST. D.S.

NEW LANDSCAPING BY OWNER

EXCAVATE HATCHED AREA FOR WATERPROOFING FIRST FLOOR WALLS NEW DRAIN TILE @ PERIM. OF BLDG. ( TYP. FOR BOTH SIDES )

D.S. NOTE #1

TYP. CHIMNEY

TYP. TURRET

TYP. MANSARD ROOF

CONNECT NEW FLOOR DRAINS INTO DOWN SPOUTS (TYP. AS INDICATED)

COURTHOUSE

NEW CONC. WALK SEE DET. B/A-4

CONC. STAIR RESTOR. PATCH, RESURFACE & RESTORE EXIST. CONC. STAIRS W/ ABCORETE AS MFR'D BY ABATRON INC. OR OTHER APPROVED BY ARCHT. FINAL SURFACE TO BE MONOLITHIC HOMOGENEOUS OF APPROVED COLOR AND TEXTURE PER ARCHT. APPROVAL BROKEN SURFACES TO BE REMOVED & REPLACED W/ ABOUELD 55-1 ABATRON INC. (1800)448-1784

FLAT ROOF

OPERATING FLUE

TOWER

HDCP PARKING

BRICK WALK & NEW CURB SEE DET. 2/SP-1

NEW PLANTING AREA

NEW 6" CURB SEE DET. 5/SP-1

SIGN

NEW FLOWERING WHITE DOGWOOD ONE OF NINE ALONG PERRY & E. WASHINGTON ST. BY OWNER

EXIST. D.S.

TYP. DORMER

D.S. NOTE #1

D.S. NOTE #2

NEW LANDSCAPING

EXIST. CONC. DECK

CLEAN OUT

LNDSCP BY OWNER

EXIST. RETAINING WALL

NEW H'RAIL

NEW CONC. DECK

EXISTING RETAINING WALL & FENCE

REPOINT EXIST. STONE WALL @ STAIRS

CONTRACT LIMIT LINE

ADD 8" P.V.C. STORM LINE 3'-0" BELOW GRADE MIN. FUTURE CONNECTION BY CITY. PROVIDE CLEAN OUT AND CAP AT PERRY ST. SIDEWALK

ONE STORY COMMERCIAL

D.S. NOTE #1 EXISTING DOWN SPOUTS TO BE CONNECTED TO NEW 8" P.V.C. STORM LINE ( NEW STORM LINE TO NEW M.H.) REMAIN

D.S. NOTE #2 EXISTING DOWN SPOUTS TO BE CONNECTED TO EXISTING SANITARY / STORM LINE. ADD (CAPPED @ GRADE) FUTURE DOWN SPOUT ADJACENT TO EXISTING. CONNECT TO NEW P.V.C. STORM LINE.

JAIL

EXIT

ENTER

VETERAN'S PLAZA

EXISTING PAVED PARKING AREA TO BE REPAVED. ALTERNATE C-1

NEW 4" PVC DRAIN TILE FROM NEW 4" PERFORATED TILE TO RETAINING WALL - SOUTH SIDE

EXIST. STEPS & LANDING TO REMAIN

REMOVE EXIST. CONC. STAIRS, RETAINING WALL & RAILING. RE-PLACE W/NEW REINF. CONC. STAIR RETAINING WALL & RAILING AS INDICATED. TIE NEW WALL INTO EXIST. W/#4 RODS (24" L.) @ 2'-0" O.C. VERT.

INDICATES 12" DEEP FTNG. BELOW GRADE

NEW H'RAIL TO MATCH EXIST.

CONC. BRIDGE

2 4'-0" DOORS

CHILLER & A.C. EQUIP. PAD BY G.C. 9' X 18' X 6"± VERIFY W/ MANUF.

EMERGENCY VEHICLES

DOG POUND (UNDER) STORAGE (OVER)

NOTE:
1. ELEVATIONS ARE NOT INDICATED AS NEW WORK SHALL FOLLOW EXISTING ELEVATIONS AND MATCH HEIGHTS OF GRADE AT THE BUILDING AND AT ABUTTING AREAS.
2. NEW LANDSCAPING TO BE DONE BY OWNER.

SITE PLAN
SCALE: 1/16" = 1'-0"

NORTH

NEW 1 1/2"Ø STEEL PIPE HANDRAIL (PAINTED)

10"± REINF. CONC. RETAINING WALL W/#4 @ 12" O.C. HOR. AND #5 @ 8" O.C. VERT. SPREAD FT'NG. (SEE PLAN FOR SIZE) TO HAVE #4 @12" EA. WAY HORIZ. AND VERT. LAYED BENT #5 @ 8" O.C. (3'-0" LLV). PROVIDE 18" MIN. GRAVEL BACKFILL TO WITHIN 6" OF GRADE. INSTALL 2" Ø SLEEVED WEEP HOLES IN WALL @ 4'-0" O.C.

EXIST. STEPS TO REMAIN

4" CONC. SLAB ON 4" GRAVEL FILL ON COMPACTED BASE

INDICATES 12" DEEP STEPPED RETAINING WALL FOOTING

C.I.P. CONC. STEPS ON COMPACTED BASE W/#4 REINF. @ 12" O.C. EA. WAY. PROVIDE MIN. 3" CONC. COVER OVER REINF.

LINE OF RETURN WALL BEYOND

NEW 4" CONC. SLAB

EXIST. GRADE

13 RISERS @ 1'-1" = 7'-1"

2 SECTION
SCALE: 3/8" = 1'-0"

6'-0" WALK

4" CONC. SLAB W/ 6x6 - 10/10 W.W.F.

1/4" C.J.

1 1/2" R.

CONT. #6 REBAR T. & B.

ASPHALT SEALER

2" ASPHALT WEARING COARSE

2" ASPHALT LEVELING COARSE

6" POROUS FILL

COMPACT SUBGRADE

CURB & WALK DETAIL
SCALE: 1" = 1'-0"

4"X8"X3" BRICK PAVER

2" SAND

4" GRAVEL

6 MIL PERF. VAPOR BARRIER

COMPACT SUBGRADE

BRICK PAVER DETAIL
SCALE: 1" = 1'-0"

NEW DOUBLE-HUNG WD. WINDOWS

EXIST. FINISHED PLASTER WALL & RETURN

WDW MANF. TO PROVIDE INT. WD. TRIM ON HEAD AND JAMB TO BE APPROVED BY ARCHT.

CAULK JOINT

EXIST. MARBLE SILL

TYP. WDW. DETAIL
SCALE: NO SCALE

2'-6"±

EXISTING WALL

GRADE

6 MIL PERFORATED VAPOR BARRIER

EXCAVATION LINE

NEW WATERPROOFING

SLOPE CEMENT WASH

POROUS FILL

4" Ø PERFORATED DRAIN TILE

12" MIN.

EXCAVATION DETAIL
SCALE: 1/2" = 1'-0"

SITE PLAN/DETAILS

REPAIR AND RESTORATION TO THE HENRY COUNTY COURTHOUSE
NAPOLEON, OHIO

GAEDE SERENE ARCHITECTS INC.
820 WEST SUPERIOR AVE. #100, CLEVELAND, OHIO 44113
PHONE (216) 241-3339 FAX (216) 241-1823
Architecture Urban Design Historic Restoration Renovation

Revisions
1 2-12-97 ADDEND. #1
2 2-21-97 ADDEND. #2
3 6-10-97

File SP-1
Job No. 9545
Date 23 JAN 97
Drawn By JRT

SP-1