

PERMIT

CITY OF NAPOLEON - BUILDING DEPARTMENT

255 West Riverview Avenue, Napoleon, Ohio 43545 - 419-592-4010

Permit No. 01568 Issued 6-20-88 date
 Job Location 226 E. Washington St. address
 Lot 90 Original Plat sub-div or legal discript
 Issued By Eldon Huber building official 599-1671
 Owner James Zumfelde 599-3451 name tel.
 Address 226 E. Washington
 Agent Self builder-eng.-etc. tel.
 Address _____
 Description of Use Residence
 Residential 1 no. dwelling units
 Commercial _____ Industrial _____
 New X Add'n. _____ Alter _____ Remodel _____
 Mixed Occupancy _____
 Change of Occupancy _____
 Estimated Cost \$ \$5500.00

ZONING INFORMATION

district G.B	lot dimensions 41.25'x165'	area 6806	front yd existing	side yds 7'-1 121r	rear yd 20'
max hgt 35'	no pkg spaces 2-min	no ldg spaces	max cover 45%	petition or appeal req'd	date appr

WORK INFORMATION:

Size: Length 22' Width 22' Stories 1 Ground Floor Area 484 s.f.
 Height 14' Building Volume (for demo. permit) _____ cu. ft.

Electrical: 1-Circuit Run from exit house panel

Plumbing: N/A brief description

Mechanical: N/A brief description

Sign: N/A Dimensions _____ Sign Area _____

Additional Information: See Plan correction sheet unattached 2-car
garage & wood deck

PAID

JUN 17 1988

Date 6-17-88 Applicant Signature James I. Zumfelde owner-agent

CITY OF NAPOLEON

INSPECTION RECORD

UNDERGROUND				ROUGH-IN					FINAL			
Type	Date	By	Type	Date	By	Type	Date	By	Type	Date	By	
PLUMBING	Building Drains			Drainage, Waste & Vent Piping			Indirect Waste			Drainage, Waste & Vent Piping		
	Water Piping									Backflow Prevention		
	Building Sewer			Water Piping			Condensate Lines			Water Heater		
	Sewer Connection									FINAL APPROVAL		
MECHANICAL	Refrigerant Piping			Refrigerant Piping			Chimney(s)			Grease Exhaust System		
				Duct Furnace(s)			Fire Dampers			Air Cond. Unit(s)		
	Ducts/Plenums			Ducts/Plenums			☐ Radiant Htr(s) ☐ Unit Htr(s)			Refrigeration Equipment		
				Duct Insulation			Pool Heater			Furnace(s)		
				Combustion Products Vents			Ventilation ☐ Supply ☐ Exhst.			FINAL APPROVAL		
ELECTRICAL	Conduits & or Cable			Conduits/Cable			☐ Range ☐ Dryer			Temp Service Temp Lighting		
	Grounding & or Bonding			Rough Wiring			☐ Generator(s) ☐ Motors			Fixtures Lampholders		
	Floor Ducts Raceways			Service Panel Switchboard			☐ Water Htr ☐ Welder			Signs		
	Service Conduit			Busways Ducts			☐ Heaters ☐ Heat Cable			Electric Mtr. Clearance		
	Temporary Power Pole			Subpanels			☐ Duct Htr(s) ☐ Furnace(s)			FINAL APPROVAL		
BUILDING	Location, Set-backs, Esmt(s)		<i>F₄</i>	Exterior Wall Construction		<i>F₄</i>	Roof Covering Roof Drainage		<i>F₄</i>	Smoke Detector		
	Excavation		<i>F₄</i>				Exterior Lath			Demolition (sewer cap)		
	Footings & Reinforcing						☐ Interior Lath ☐ Wallboard					
	Floor Slab			Interior Wall Construction			Fire Wall(s)			Building or Structure	<i>7/19 BD</i>	
	Foundation Walls		<i>F₄</i>	Columns & Supports			Fireplace Chimney					
	Sub-soil Drain			Crawl Space ☐ Vent ☐ Access			Attic ☐ Vent ☐ Access					
	Piles			Floor System(s)						FINAL APPROVAL BLDG. DEPT.	<i>7/19 BD</i>	
				Roof System			Special Insp Reports Rec'd			Certificate of Occupancy Issued		
ADDITIONAL	INSPECTIONS, CORRECTIONS, ETC.					INSPECTIONS, CORRECTIONS, ETC.						
	TRUSSES NOT AS SHOWN ON TROSS DIAGRAM.											
	Trusses meet Min. Sds, <i>7/19 BD</i>											

RESIDENTIAL PLAN CORRECTION SHEET

CITY OF NAPOLEON
55 West Riverview Ave.
Napoleon, Ohio 43545
19/592-4010

ADDENDUM TO Permit No. 01568
Owner JAMES ZUMPELDE
Contractor SELF
Location 226 E. WASHINGTON

1e. note the items checked below and incorporate them into your plans as indicated: ☐ PERMIT NOT
ET ISSUED, CORRECT PLANS AND RE-SUBMIT. ☒ PERMIT ISSUED, INCORPORATE ITEMS DURING CONSTRUCTION.

GENERAL		Show size of members supporting porch roof.	
☒ Provide approved smoke detector(s) as req'd. <u>EXISTING</u>		Provide double top plate for all bearing partitions and exterior walls.	
Provide 1/2" gypsum wallboard between dwelling and garage, on garage side.		Provide design data for prefab wood truss.	
Provide min. 1 3/8" solid wood door from garage to dwelling. (or equal)		Ceiling joists undersized in _____.	
Submit fully dimensioned plot plan.		Roof rafters undersized in _____.	
☒ Provide min. of 1-3'0" x 6'8" exit door.		PLUMBING AND MECHANICAL	
Provide min. 22" x 30" attic access opening.		Terminate all exhaust systems to outside air.	
Provide min. 18" x 24" crawl space access opening.		Insulate ducts in unheated areas.	
Provide approved sheathing or flashing behind masonry veneer.		Provide backflow prevention device on all hose bibs.	
Provide min. 15# underlayment on roof.		Terminate pressure and temperature relief valve drain in an approved manner.	
Provide adequate fireplace hearth.		Provide dishwasher drain with approved air gap device.	
Install factory built fireplaces/stoves according to manufacturers instructions.		METAL VENEERS	
Terminate chimney 2' above roof or 2' above highest point of building within 10' of chimney.		Contact City Utilities Dept. to remove conductors and/or meter.	
		Provide approved system of grounding and bonding.	
LIGHT AND VENTILATION		ELECTRICAL	
Provide mechanical exhaust or window in bathroom _____.		Show location of service entrance panel and service equipment panel.	
Provide min. _____ Sq. In. net free area attic ventilation.		G. F. C. I. req'd. on temporary electric.	
Provide min. _____ Sq. In. net free area crawl space ventilation.		Outdoor, bathroom and garage receptacles shall be protected by G. F. C. I.	
FOUNDATION		Maximum number of receptacles permitted on a G. F. C. I. circuit shall be 10 for 20 A. circuits and 7 for 15A. circuits.	
Min. depth of foundation below finished grade is 32".		Refrigerators, microwaves, washers, disposal, furnace and air conditioners shall be on separate circuits.	
Min. size of footer _____" x _____".		INSPECTIONS	
Provide anchor bolts 1/2" @ 6' o.c. 1' from each corner. Embedded 7" in concrete and 15" in masonry.		The following indicated inspections are required. The owner or his agent shall contact the City Building Dept. at least 24 hrs prior to the time the inspection is to be made.	
Show size of basement columns.		☒ Footers and Setbacks.	
FRAMING		Building sewer.	
Show size of wood girder in _____.		☒ Foundation.	
Provide design data for structural member in _____.		HVAC rough-in.	
Floor joists undersized in _____.		☒ Plumbing rough-in.	
Provide double joists under parallel bearing partitions.		Final Building	
Provide 1" x 4" let in corner bracing, approved sheathing, or equal.		Plumbing final.	
Show size of headers for openings over 4' wide _____.		Electrical service.	
		☒ Electrical rough-in.	
		☒ Electrical final	

Additional Corrections. _____

The approval of plans and specifications does not permit the violation of any section of the Building Code or other City Ordinance. This addendum is attached to Permit No. 01568 and made a part thereof. DATE APPROVED OR DISAPPROVED 6-20-88 Checked by ELDON HOBER
Plan Examiner.

DATE RECHECKED AND APPROVED _____

Checked by _____

GENERAL NOTES:

1. All plates shown are 20 gauge ILS plates, unless otherwise noted. Plates to be applied on both faces of each joint and centered, unless plate position is dimensioned.
2. Provide continuous lateral bracing to bottom chord at maximum intervals of 10'-0" at the date of drawing.
3. Design is based substantially on current applicable standards of T.P.I. and N.D.S.
4. ■ Denotes continuous lateral bracing in addition to that described in General Notes 2.
5. Provide continuous lateral support of top chord by means of plywood sheathing or properly spaced purlins.

DESCRIPTION:

SPAN:	DRAWING NO.:	DATE:
PITCH/DEPTH:		SHT. OF
DRAWN BY:	ENG. BY:	CHECKED BY:


ATTENTION: Erection, Handling, Safety Precautions, Temporary or Permanent Bracing of trusses are not the responsibility of the Truss Designer, Metal Connector Plate Manufacturer, or the Truss Manufacturer and therefore are not a part of these engineering drawings. Trusses are designed as individual components. All lateral bracing specified on these truss drawings are intended to provide lateral restraint to individual truss members only. The design, amount and proper installation of temporary or permanent bracing for whatever reason is the sole responsibility of the designer or builder of the complete structure. Adequate Bracing is Always Required. Competent professional advice should always be obtained relative to truss bracing and erection requirements.

Uniform Loading
 Top L1/4s 25.0 11'-1 3x8 5) 3x4
 Top Deck 10.0 2) 3x2 6) 3x2
 Bot. L1/4s 10.0 3) 3x4 7) 3x8
 Bot. Deck 10.0 4) 3x4
 Spacing (O.C.): 24.0 LEFT HEEL HT. 3 -15
 J'N. Section. occurs 1.15 RIGHT HEEL HT. 3 -15
 Number of Plates 1
 Reaction At 1: 1210
 Reaction At 7: 1210
 CAMBER 2 1/8

Discontinuities
 a) 1 0 0
 b) 1 0 0
 c) 3 11 15

CHORDS
VEBS

CHORDS 2x4 MSR SPR-PINE-TR 1500F-1.3
VEBS 2x4 Spruce Pine-fir No. 3



1	2	2892	C 3	5	1752	T 5	8	395	C
2	4	2420	C 5	7	2554	T			
4	6	2420	C 2	3	395	C			
6	7	2892	C 3	4	800	T			
1	3	2554	T 4	5	890	T			

Total Span = 22ft 0in 0/16
 Total Height = 3ft 11in 15/16
 169 ID = DEF22

De fiance

Att. Greg

CITY OF NAPOLEON

255 W. Riverview

NAPOLEON, OHIO 43545

message

reply

to

JAMES ZUMFELD

226 E. WASHINGTON

NAP. OHIO 43545

subject GARAGE @ 226 E. WASH.

THE TRUSSES YOU HAVE SUBMITTED

DO NOT MEET THE MIN BOT. CORD

LOADING REQUIREMENTS OF C.A.B.O.

MIN REQ. 10# P.S.F. LIVE + 10# P.S.F. DEAD.

TOTAL 20# P.S.F. YOU HAVE 2. OPTIONS, EITHER

REPLACE THE TRUSSES WITH ONES THAT WILL

THE CODE OR STRENGTHEN THE

TRUSS AS DIRECTED BY THE MANUFACTURER,

TO SUPPORT THE REQUIRED LOADS.

date 11-4-88 signed ELDON HUBER

date signed

SENDER: Mail white and pink copies with carbon intact.

RECEIVER: Reply, retain white copy, return pink copy.

CITY OF NAPOLEON
235 W. Riverview
NAPOLEON, OHIO 43545

message

reply

to

James Somerville

556 E. Washington

Map Ohio 47747

subject

James Somerville 556 E. Main

THE TRUCKER YOU HAVE SUBMITTED

DO NOT MEET THE MIN. RAT. CODE

LOADING REQUIREMENT OF C.R.B.D.

MIN. R.P. 10*125 CUBIC YD. 10*125. 0.000

TOTAL 50*125. YOU HAVE 5.000000, 0.000000

REPLACE THE TRUCKER WITH ONE THAT WILL

MEET THE CODE OR STRENGTHEN THE

TRUCK AT DIRECTED BY THE MANUFACTURER,

TO SUPPORT THE REQUIRED LOADS.

date 11-4-88 signed E. J. Harker

RECEIVER: Reply, retain white copy, return pink copy.

SENDER: Mail white and pink copies with carbon intact.

© 1982 American Printing and Litho Corp., Amsterdam, N.Y. 12010

LOADING TOP CHORD 37.0 PSF BOTTOM CHORD 10.0 PSF
 STRESS INCREASE 1.15 PITCH 4.0/12 4/2.0 PANELS
 SPACING 24 IN. ON CENTER

LUMBER SPECIFICATIONS

2X 4 #2 SO. PINE (KD)	1550FB
2X 4 #2 DEN SO. PINE (KD)	1800FB
2X 4 #1 SO. PINE (KD)	1850FB
2X 4 #1 DEN SO. PINE (KD)	2150FB
2X 4 SEL S SO. PINE (KD)	2150FB
2X 4 DEN S S SO. PINE (KD)	2500FB
2X 6 #2 SO. PINE (KD)	1300FB
2X 6 #2 DEN SO. PINE (KD)	1550FB
2X 6 #1 SO. PINE (KD)	1600FB
2X 6 #1 DEN SO. PINE (KD)	1850FB
2X 6 SEL S SO. PINE (KD)	1850FB
2X 6 DEN S S SO. PINE (KD)	2200FB

MAXIMUM OUT TO OUT SPAN

TOP CHORD		BOT CHORD	
W/ 2X4	W/ 2X6	W/ 2X4	W/ 2X6
BOT CH	BOT CH	BOT CH	BOT CH
27'-4"	28'-0"	22'-10"	22'-10"
29'-11"	30'-0"	25'-1"	25'-1"
30'-6"	30'-7"	25'-3"	25'-3"
32'-3"	32'-4"	27'-10"	27'-10"
32'-0"	32'-1"	28'-1"	28'-1"
33'-7"	33'-8"	30'-10"	30'-10"
40'-2"	41'-0"	31'-2"	31'-2"
43'-11"	44'-0"	34'-6"	34'-6"
45'-1"	45'-2"	37'-7"	37'-7"
47'-5"	47'-6"	41'-4"	41'-4"
47'-0"	47'-1"	41'-0"	41'-0"
49'-3"	49'-3"	45'-1"	45'-1"

WEB MATERIAL

2"x4" Standard Spruce Pine Fir
 2"x4" Standard Hem Fir
 2"x4" No. 3 Southern Pine (KD)

SPAN TO


32 Ft.
 32 Ft.
 32 Ft.

GENERAL NOTES:

- 1) All plates to be pressed on both faces of each joint and centered about joint interface unless otherwise dimensioned.
- 2) * Denotes plate sizes to be used in conjunction with 2"x4" chord sizes only.
- 3) ** Denotes plate sizes to be used in conjunction with 2"x6" chord sizes only.
- 4) Provide continuous lateral bracing to bottom chord at maximum intervals of 10' - 0".





Field Erection, Handling, Safety Precautions, Bracing of Trusses are not the responsibility of the Truss Manufacturer, Designer, or the Metal Connector Plate Manufacturer; and therefore, is not a part of these engineering drawings. Professional advice should be sought relative to Erection, Handling & Bracing.



LOADING AND BAR FORCE DIAGRAM


PLATE	SPAN TO
4x6*	32'
5x6	32'

PLATE	SPAN TO
5x8	32'



DETAIL A

DETAIL B



DESIGN CRITERIA TPI - 78		DESCRIPTION KINGPOST W/DIAG.		DRAWN BY	
SPAN VARIABLE		REMARKS		ENGINEERED BY	
PITCH / DEPTH 4/12				CHECKED BY	
DATE		NO. REVISIONS		BY	
INTER-LOCK STEEL COMPANY 3678 East State Street Sharon, Pennsylvania 16146				DRAWING NO. 2-K/D-47-15-4	

PERMIT

CITY OF NAPOLEON - BUILDING DEPARTMENT

255 West Riverview Avenue, Napoleon, Ohio 43545 - 419-592-4010

Permit No. 01906 Issued 1-29-90
date
 Job Location 408 E. Washington
address
 Lot 83A Original Platt
sub-div or legal discript
 Issued By Eldon Huber
building official
 Owner Thelma Sonnenberg 592-1299
name tel.
 Address 408 E. Washington
 Agent Northwestern Ohio CAC 784-5393
builder-eng.-etc. tel.
 Address 1933 2nd Street Defiance
 Description of Use Residence
 Residential 1
no. dwelling units
 Commercial _____ Industrial _____
 New _____ Add'n. _____ Alter _____ Remodel X
 Mixed Occupancy _____
 Change of Occupancy _____
 Estimated Cost \$ 410.00

FEES	BASE	PLUS	TOTAL
☒ BUILDING	9.00	.00	9.00
☐ ELECTRICAL			
☐ PLUMBING			
☐ MECHANICAL			
☐ DEMOLITION			
☐ ZONING			
☐ SIGN			
☐ WATER TAP			
SEW. INSP.			
SEWER TAP			
TEMP. WATER			
TEMP. ELECT.			
ADDITIONAL PLAN REVIEW	Struct. _____ hrs		
	Elect. _____ hrs		
TOTAL FEES.....			9.00
LESS MIN. FEES PAID _____			
	date		
BALANCE DUE.....			

ZONING INFORMATION

district	lot dimensions	area	front yd	side yds	rear yd
max hgt	no pkg spaces	no ldg spaces	max cover	petition or appeal req'd	date appr

WORK INFORMATION:

Size: Length _____ Width _____ Stories 1 Basement Fl. Area 1008
 Second Floor Area X
 Ground Floor Area 1242
 Height _____ Building Volume (for demo. permit) 9936 cu. ft.

Electrical: _____ brief description _____
 Plumbing: _____ brief description _____
 Mechanical: _____ brief description _____

Sign: _____ Dimensions _____ Sign Area _____
type

Additional Information: Insulate floors in crawlspaces, blow insulation into sidewalls
replace broken glass & weatherstrip windows and doors, insulate hot water heater & wrap
ducts in crawlspaces

Date _____ Applicant Signature _____ **JAN 26 1990**
owner-agent

INSPECTION RECORD

UNDERGROUND			ROUGH-IN			FINAL		
Type	Date	By	Type	Date	By	Type	Date	By
PLUMBING	Building Drains		Drainage, Waste & Vent Piping			Indirect Waste		
	Water Piping							
	Building Sewer		Water Piping			Condensate Lines		
	Sewer Connection							
						FINAL APPROVAL		
MECHANICAL	Refrigerant Piping		Refrigerant Piping			Chimney(s)		
			Duct Furnace(s)			Fire Dampers		
	Ducts/ Plenums		Ducts/ Plenums			☐ Radiant Htr(s) ☐ Unit Htr(s)		
			Duct Insulation			Pool Heater		
			Combustion Products Vents			Ventilation ☐ Supply ☐ Exhst.		
						FINAL APPROVAL		
ELECTRICAL	Conduits & or Cable		Conduits/ Cable			☐ Range ☐ Dryer		
	Grounding & or Bonding		Rough Wiring			☐ Generator(s) ☐ Motors		
	Floor Ducts Raceways		Service Panel Switchboard			☐ Water Htr ☐ Welder		
	Service Conduit		Busways Ducts			☐ Heaters ☐ Heat Cable		
	Temporary Power Pole		Subpanels			☐ Duct Htr(s) ☐ Furnace(s)		
						FINAL APPROVAL		
BUILDING	Location, Set-backs, Esmt(s)		Exterior Wall Construction			Roof Covering Roof Drainage		
	Excavation					Exterior Lath		
	Footings & Reinforcing					☐ Interior Lath ☐ Wallboard		
	Floor Slab		Interior Wall Construction			Fire Wall(s)		
	Foundation Walls		Columns & Supports			Fireplace Chimney		
	Sub-soil Drain		Crawl Space ☐ Vent ☐ Access			Attic ☐ Vent ☐ Access		
	Piles		Floor System(s)					
						FINAL APPROVAL BLDG. DEPT.		
						Certificate of Occupancy Issued		
ADDITIONAL	INSPECTIONS, CORRECTIONS, ETC.					INSPECTIONS, CORRECTIONS, ETC.		

LEGAL NOTICE

Date 3-1-90

WHEREAS, violations of { Article _____, Section _____ of the Zoning Ordinance }
{ Article _____, Section R-109 of the Building Code } have been found on
{ Article _____, Section _____ of the _____ Code }
these premises, IT IS HEREBY ORDERED in accordance with the above Code that all persons cease, desist
from, and

STOP WORK

instruction, alterations or repairs on these premises

E. WASHINGTON

order or removing or mutilating this notice are liable to arrest
the Department.

ECON HUBER

BUILDING OFFICIAL



3-1-90 425 E.
E. WASHINGTON

PERMIT

CITY OF NAPOLEON - BUILDING DEPARTMENT

255 West Riverview Avenue, Napoleon, Ohio 43545 - 419-592-4010

Permit No. 01931 Issued 3-15-90
date
 Job Location 529 E. Washington
address
 Lot 15 n.pt. RK Scotts First Addition
sub-div or legal discript
 Issued By Eldon Huber
building official
 Owner Elda Long 599-8556
name tel.
 Address 529 E. Washington
 Agent Jerry Tonjes
builder-eng.-etc. tel.
 Address 825 Hobson
 Description of Use Residence
 Residential 1
no. dwelling units
 Commercial _____ Industrial _____
 New _____ Add'n _____ Alter X Remodel _____
 Mixed Occupancy _____
 Change of Occupancy _____
 Estimated Cost \$ 9500.00

FEES	BASE	PLUS	TOTAL
☒ BUILDING	9.00	48.00	57.00
☒ ELECTRICAL	15.00	60.00	75.00
☒ PLUMBING	9.00		9.00
☒ MECHANICAL	18.00		18.00
☒ DEMOLITION			
☐ ZONING			
☐ SIGN			
☐ WATER TAP			
SEW. INSP.			
SEWER TAP			
TEMP. WATER			
TEMP. ELECT.			
ADDITIONAL PLAN REVIEW	Permit no. 01223	Struct. _____ hrs	6.00
		Elect. _____ hrs	
TOTAL FEES.....			165.00
PAY IN 1983			
LESS MIN. FEES PAID			90.00
		date	
BALANCE DUE.....			75.00

ZONING INFORMATION

district	lot dimensions	area	front yd	side yds	rear yd
C					
max hgt	no pkg spaces	no ldg spaces	max cover	petition or appeal req'd	date appr

WORK INFORMATION:

Size: Length _____ Width _____ Stories _____ Ground Floor Area _____

Height _____ Building Volume (for demo. permit) _____ cu. ft.

Electrical: 20 new circuits

brief description

Plumbing: Install new bathtub

brief description

Mechanical: NEW HIGH EFF FURNACE & NEW HOT AIR ROUS

brief description

Sign: _____ Dimensions _____ Sign Area _____

type

Additional Information: Put bathtub in, put one wall in bathroom; one wall in bedroom trim work; install new windows, size varies

Date _____ Applicant Signature _____
owner-agent

FIELD CORRECTION NOTICE

LOCATION 529 E. WASHINGTON PERMIT NO. 01721

ISSUED TO ELDA LONG
PERMIT HOLDER AND/OR ALL RESPONSIBLE PARTIES.

NOTICE DELIVERED TO ELDA LONG 529 E. WASHINGTON

Upon inspection, violations of the C.A.L.D. 4 H.E.C. Sec. were in evidence.

The following orders are hereby issued for their correction: SEE ATTACHED LIST

PLEASE CALL FOR INSPECTION WHEN CORRECTIONS HAVE BEEN COMPLETED. ACCEPTANCE AND APPROVAL BY AN INSPECTOR OF THIS DEPARTMENT IS REQUIRED AND MUST BE CORRECTED

ON OR BEFORE REFER TO ATTACHED COPY

DATE 3-15-90

BY ELDA LONG
INSPECTOR

PINK - ORIGINAL COPY WHITE - FIELD COPY YELLOW - FILE COPY

March 20, 1990

Field Correction Notice
529 E. Washington
Permit No. 01931

Item No. 1: Extend a Type B vent from the water heater located in the basement up thru the first floor, the attic and the roof with an approved weather lap.

Note: Provide minimum clearances to combustible materials as required by the type of vent.

Item No. 2: Install a cover on the garage electrical panel.

Item No. 3: Install covers on all spare circuit spaces in electrical panels.

Item No. 4: Install connection boxes for all electrical wire splices.

Item No. 5: Install covers on all switch boxes, outlet boxes and unused light boxes.

Item No. 6: Minimum wire size for 15 amp circuits = 14 GA.

Minimum wire size for 20 amp circuits = 12 GA.

Replace all 20 amp breakers servicing 14 GA. wire with 15 amp breakers.

Item No. 7: Furnish ground fault protection for all outlets within 6 ft. of the kitchen sink.

Item No. 8: Label all circuits on the panel doors.

Item No. 9: Add one outlet on the family room south wall.

Item No. 10: Provide a connection box for the attic ventilation fan.

Item No. 11: Provide two smoke detectors. One on first floor on ceiling between the bedroom doors, and one in the basement.

Item No. 12: Provide a duct from the bathroom exhaust fan thru the attic to the outside.

- Item No. 13: Provide additional attic ventilation total vent area required one square foot per 300 square feet of attic area.
- Item No. 14: Provide additional supports for the basement ductwork.
- Item No. 15: Provide 3' X 3' stoops not more than 8 1/2" below the thresholds of both exterior doors. Also provide stair steps as required, minimum TR = 9", maximum RI = 8 1/4".
- Item No. 16: Provide 1/2" drywall on the garage side of the wall separating the house from the garage.

The items listed must be completed within the time allotted below.

Item No. 1 and 11 - before March 23, 1990

Item No. 2, 3, 4, 5, 6, 7, 8, 9, 10, and 12 - before April
16, 1990.

Item No. 12, 13, 14, 15, and 16 - before September 15, 1990.

Elda Long
Signature

4-16-90
Date

CITY OF NAPOLEON

255 W. Riverview
NAPOLEON, OHIO 43545

message

reply

to ELDA LONG
529 E. WASHINGTON
NAPOLEON, OHIO 43545

subject BUILDING PERMIT

YOUR BUILDING PERMIT HAS BEEN
ISSUED AND SHOULD BE PICKED
UP AT THE CITY BUILDING.

PERMIT NO 01931 FEE 165.⁰⁰

ASK TO SEE ME WHEN YOU STOP IN

WOULD LIKE TO GO OVER THE
PLAN CORRECTION SHEET WITH YOU.

date 3-30-90 signed ELDON HUBER

SENDER: Mail white and pink copies with carbon intact.

date _____ signed _____

RECEIVER: Reply, retain white copy, return pink copy.

SENDER: Mail white and pink copies with carbon intact.

RECEIVER: Reply, retain white copy, return pink copy.

date 2-20-50 signed E. C. HUBER

date signed

FROM CORRECTION CHECK WITH YOU.

WANTO LIKE TO GO OVER THE

AK TO SEE ME WHEN YOU STOP IN

PERMIT NO. 0191 FEE 167.00

UP AT THE CITY BUILDING.

THROU AND THROU DE PICKED

YOUR BUILDING PERMIT AND BEEN

subject

Building PERMIT

NAPOLEON, OHIO 43545

259 E. WASHINGTON

FROM LOUD

message

reply

NAPOLEON, OHIO 43545
255 W. River View
CITY OF NAPOLEON

FIELD CORRECTION NOTICE

LOCATION 226 E. WASHINGTON PERMIT NO. 01568

ISSUED TO JAMES ZUMFELDE
PERMIT HOLDER AND/OR ALL RESPONSIBLE PARTIES.

NOTICE DELIVERED TO JAMES ZUMFELDE 226 E WASHINGTON

Upon inspection, violations of the _____ Sec. _____ were in evidence.

The following orders are hereby issued for their correction: _____

PROVIDE CORNER BRACING ON YOUR SOUTH WALL
AND ON YOUR NORTH WALL BETWEEN THE END
OF THE GARAGE DOOR + THE CORNER,

I NOTE THAT THE TRUSSES YOU INSTALLED DO NOT
MATCH THE TRUSS DIAGRAM YOU SUBMITTED. SEE
ATTACHED COPY. RESUBMIT A TRUSS DIAGRAM FOR
THE TRUSSES INSTALLED.

PLEASE CALL FOR INSPECTION WHEN CORRECTIONS HAVE BEEN COMPLETED. ACCEPTANCE
AND APPROVAL BY AN INSPECTOR OF THIS DEPARTMENT IS REQUIRED AND MUST BE CORRECTED

ON OR BEFORE _____.

DATE 8-11-88

BY ELDON HUBER
INSPECTOR

PINK - ORIGINAL COPY WHITE - FIELD COPY YELLOW - FILE COPY

FIELD CORRECTION NOTICE

LOCATION 226 E. WASHINGTON PERMIT NO. 01568

ISSUED TO JAMES ZUMFELDE
PERMIT HOLDER AND/OR ALL RESPONSIBLE PARTIES.

NOTICE DELIVERED TO JAMES ZUMFELDE 226 E. WASHINGTON

Upon inspection, violations of the _____ Sec. _____ were in evidence.

The following orders are hereby issued for their correction: _____

PROVIDE CORNER BRACING ON YOUR SOUTH WALL
AND ON YOUR NORTH WALL BETWEEN THE END
OF THE GARAGE DOOR + THE CORNER.

I NOTE THAT THE TRUSSES YOU INSTALLED DO NOT
MATCH THE TRUSS DIAGRAM YOU SUBMITTED. SEE
ATTACHED COPY. RESUBMIT A TRUSS DIAGRAM FOR
THE TRUSSES INSTALLED.

PLEASE CALL FOR INSPECTION WHEN CORRECTIONS HAVE BEEN COMPLETED. ACCEPTANCE
AND APPROVAL BY AN INSPECTOR OF THIS DEPARTMENT IS REQUIRED AND MUST BE CORRECTED

ON OR BEFORE _____

DATE 8-11-88

BY ELDON HUBER
INSPECTOR

PINK - ORIGINAL COPY WHITE - FIELD COPY YELLOW - FILE COPY

PERMIT

CITY OF NAPOLEON - BUILDING DEPARTMENT

01568 255 West Riverview Avenue, Napoleon, Ohio 43545 - 419-592-4010

Permit No. Issued 6-20-88

Job Location 226 E WASHINGTON

Lot 90 ORIGINAL PLAT

Issued By E

Owner JAMES COMFELDES JR

Address 226 E. WASHINGTON

Agent SELF

Description of Use RESIDENTIAL

Residential 1

Commercial Industrial

New X Add'n. Alter Remodel

Mixed Occupancy

Change of Occupancy

Estimated Cost \$ 5500.00

FEES	BASE	PLUS	TOTAL
BUILDING	9.00	40.00	49.00
ELECTRICAL	15.00	3.00	18.00
PLUMBING			
MECHANICAL			
DEMOLITION			
ZONING			
SIGN			
WATER TAP			
SEWER TAP			
TEMP. ELECT.			
ADDITIONAL PLAN REVIEW	Struct. <u> </u> hrs	Elect. <u> </u> hrs	
TOTAL FEES	67.00		
LESS MIN. FEES PAID	date <u> </u>		
BALANCE DUE			

ZONING INFORMATION

district	lot dimensions	area	front yd	side yds	rear yd
G.D	41.25' x 165'	6806	15' EXISTING	7'-L 12'-R	20'
max hgt	no pkg spaces	no ldg spaces	max cover	petition or appeal req'd	date appr
35'	2-MIN		45%		

WORK INFORMATION:

Size: Length 22' Width 22' Stories 1 Ground Floor Area 484 S.F.

Height 14' Building Volume (for demo. permit) cu. ft.

Electrical: 1-CIRCUIT RUN FROM EXIST HOUSR PANEL

Plumbing: NA

Mechanical: NA

Sign: NA Dimensions Sign Area

Additional Information: SEE PLAN CORRECTION SHEET

UNATTACHED 2-CAR GARAGE & WOOD DECK

Date Applicant Signature owner-agent

CITY OF NAPOLEON
BUILDING INSPECTION DEPARTMENT
APPLICATION FOR BUILDING PERMIT
(Please print or type)

The undersigned hereby makes application for construction, installation, or alteration work as herein specified, agreeing to do all such work in strict accordance with the City of Napoleon's adopted Building Codes.

Location of project 226 E. Washington Cost of project \$ 5300
Owner's Name James Zumfardo Address 226 E. Washington
Contractor James Zumfardo Telephone No. 592-2451
Address 226 E. Washington

Lot Information: (Not required for siding job)

Lot No. 90 Subdivision Original Plat
Zoning District 6B Lot Size 41.0 ft. X 165 ft. Area 6765 sq. ft.
Setbacks: Front _____ Right Side 5' Left Side 5' Rear 10'

Work Information:

Residential X Commercial _____ Industrial _____
New Construction X Addition _____ Remodel _____
Accessory Building X Siding Vinyl
(Specific Type)

Brief Description of Work: ----- Garage + Deck

Size: Length 22 Width 22 No. of Stories 1
Area: 1st Floor _____ sq. ft. Basement _____ sq. ft.
2nd Floor _____ sq. ft. Accessory Bldg. 484 sq. ft.
3rd Floor _____ sq. ft. Other Deck 160 sq. ft.

Additional Information: _____

APPLICATION FOR PERMIT SHALL BE ACCOMPANIED BY TWO COMPLETE SETS OF PLANS INCLUDING: ELEVATIONS, FLOOR PLANS, CROSS SECTIONS AND PLOT PLAN. IF ADDITION OR REMODELING, SHOW ALL EXISTING STRUCTURES AND THEIR SIZE AND LOCATION. ALL PLANS SHALL BE DRAWN TO SCALE.

Date 6-17-88 Applicant's Signature James D. Zumfardo

PERMIT NO.

PERMIT FEE \$

CITY OF NAPOLEON
BUILDING INSPECTION DEPARTMENT
APPLICATION FOR ELECTRICAL PERMIT
(Please print or type)

The undersigned hereby makes application for installation or replacement of electrical equipment as herein specified, agreeing to do all such work in strict accordance with the City of Napoleon's adopted Electrical Codes.

Owner's Name James Zumfelde Address 226 E. Washington

Electrical Contractor James Zumfelde Telephone No. 599-1671

Address 226 E. Washington

General Contractor James Zumfelde Telephone No. 599-1671

Address 226 E. Washington

Location of Project 226 E. Washington Cost of Project _____

Work Information:

Residential X Commercial _____ Industrial _____

No. Units _____

New _____ Service Change _____ Rewiring _____ Additional Wiring _____

Brief Description of Work: Lights & Outlet in Garage

Size of proposed service entrance N/A Number of new circuits 1

Type of proposed service entrance N/A Underground ~~_____~~ Overhead ~~_____~~

Require Temporary Electric NO (Yes or No)

Total Floor Area - Commercial and Industrial only _____ sq. ft.

Additional Information: _____



*Ground fault circuit interrupter protection is required on all 120-volt single phase, 15 and 20 amp. Circuits which are part of a temporary electric service; and also on bathroom, outdoor, and garage receptacles in all dwelling units. Art. 220-8 N.E.C.


Application for permit shall be accompanied by two complete sets of plans including: Electrical layout and riser diagram. (For commercial and industrial work only).


ate 6-17-88 Applicant's Signature James Zumfelde


PERMIT NO. _____

PERMIT FEE \$ _____











REAR



221
Side



22'
Side

